

# Town of Bethel

## Highway Department

6 Sympaug Park Rd,  
Bethel, Connecticut 06801  
(203) 794-8549 Fax: (203) 794-8144

***Robert Dibble, Highway Superintendent***

Dear Resident,

The Town of Bethel Highway Department has completed repairs and installation of storm water drainage on ***Nashville Rd. from Nashville Ext. to Rt. 53*** in preparation for rebuilding of the road surface. The following schedule includes information that you will find useful during this process. Please be aware that the road will be closed daily to through traffic during our operations, although emergency and school bus traffic will not be interrupted. ***Residents that live within the project will have access.*** Please drive carefully, as you may encounter short delays. The daily road closures assist us in providing a safe work zone for our employees and completion of the project in a timely manner.

The scope of this project will include a full depth reclamation of the bituminous surface and subgrade materials, grading and compaction of the reclaimed material, and the application of liquid calcium chloride. This will leave a loose gravel road surface for a short period of time. A two layer bituminous overlay will be installed over the gravel surface, followed by the installation of driveway aprons to match the new road surface. Curbing will only be installed in areas that are prone to erosion, and areas that cause water run off problems.

While the road is being prepared for the bituminous overlay, airborne dust from the gravel surface may occur. We will make every attempt to keep this occurrence at a minimum. You may encounter short delays while traveling on the road. Please keep in mind that the safety of our employees as well as the residents is our primary concern. We will work diligently to ensure that this project is completed in a timely manner, although conditions such as weather, equipment failures and schedules for contracted services can affect our proposed schedule.

Thank you in advance for your cooperation. **Please drive carefully**

### **Schedule:**

- |   |  |
|---|--|
| <b>1: Full Depth Reclamation</b>              | <b>8/16/2016 thru 8/19/2016</b>              |
| <b>2: Fine Grading and Compaction</b>         | <b>8/16/2016 thru 8/24/2016</b>              |
| <b>3: Bituminous Paving</b>                   | <b>8/24/2016 thru 8/29/2016</b>              |
| <b>4: Driveway Aprons &amp; Curbing</b>       | <b>approx. 20 days after paving</b>          |
| <b>5: Final clean up, topsoil and seeding</b> | <b>following Driveway Apron installation</b> |

**Scheduled dates may change to allow project completion prior to actual schedule**

**If you would like more information on *full depth reclamation* or *sub base stabilization* please go on the internet and perform a search.**

