



40 Whittemore Road, Middlebury CT 06762
Tel • (203)758-1077 Fax • (203)758-9519
Email • ccc@ctcombustion.com
Web • www.ctcombustion.com

10/25/23

Town of Bethel
1 School Street
Bethel, CT 06801

Attn.: Mr. Eric Swensen, Director of Public Works
Cc: Mr. Greg Rux, Facility Mgr.
Re.: Bethel Municipal Center: Pumps/Control

Dear Mr. Swenson:

Per your request, below please find our proposal for installation of differential pressure control sensors and piping and each hydronic pump set at the Bethel Municipal Center. This submission is to serve as an accompanying proposal to the work summary submitted by SNE Building Systems for hydronic pump variable frequency drive (VFD) control at the facility.

Accordingly, this proposal includes the following:

- A) Installation of isolation/service valves at the suction and discharge tapplings of each pump (discharge tapping at the system side of the multipurpose valve)
- B) Installation of Type 'L' soft copper tubing/piping from each zone pumpset; piping to be installed as suction and discharge common manifold piping for each zone
- C) Mounting/support and piping installation of six (6) differential pressure sensors for detection of zone pump operation and zone differential pressure, for VFD control for each circulating pump and each respective zone (sensors supplied by SNE)

Pricing for this work, complete as detailed, is as follows:

TWO THOUSAND TWO HUNDRED AND TWENTY DOLLARS (\$2,220.00)

We hope this information is helpful to you. Please contact us at (203)223-3083 (cell) upon your review if you have any questions or require further assistance.

Regards,

Dean A. Pietrorazio
President





CONNECTICUT COMBUSTION CORPORATION